

MEETING DATE: October 14, 2025

STAFF PERSON RESPONSIBLE: Deborah E. Kula, P.E., Special Projects Engineer

DESCRIPTION: Construction Contract with Inliner Solutions, LLC for the Highlands Ranch Small Storm Sewer UV CIPP Lining Project in the Amount of \$275,000.00, Douglas County Project # SP 2025-015.

SUMMARY: The Project will repair 1,067 linear feet of 15-36 inch corrugated metal pipe (CMP), in various locations within Highlands Ranch. These pipes were identified by the storm sewer video program as needing maintenance. These systems will be rehabilitated with Ultraviolet Cured in Place Pipe (UV CIPP); this process provides the least amount of disruption, the least amount of environmental impacts, and the strongest pipe rehabilitation. These safety improvements will extend the service life of these pipes.

County staff requested quotes from five contractors that have completed similar work for the County in the past to be able to complete the Project as soon as possible. The quotes received are as follows:

Inliner Solutions, LLC	\$241,146.00
Insituform Technologies	\$255,635.00
MOCON Pacific	\$278,085.00
American West Construction	\$293,350.00
<u>Snowbridge, Inc.</u>	<u>Too Busy</u>
Engineer's Estimate	\$276,063.00

Inliner Solutions, LLC was the most cost-effective for this project throughout Highlands Ranch.

The contract with Inliner Solutions, LLC will be for a total of \$275,000.00, which includes \$33,854.00 in Field Modifications as contingency for any additional work items that arise (and are approved by the County in writing) during construction for the project.

Funding for this construction contract is set aside in Fund 200, Business Unit

800506.478300.

**RECOMMENDED
ACTION:**

Approval of the Construction Contract with Inliner Solutions, LLC for the Highlands Ranch Small Storm Sewer UV CIPP Lining Project in the amount of \$275,000.00, Douglas County Project # SP 2025-015.

REVIEW:

Kristina Mann	Approve	9/26/2025
Jeff Garcia	Approve	10/6/2025
Christie Guthrie	Approve	10/7/2025
Doug DeBord	Approve	10/9/2025

ATTACHMENTS:

Contract Inliner Solutions -SP2025-015 HR Small UV CONSTRUCTION -Debbie k