

EXHIBIT B
BID SCHEDULE

Item No.	Description	Units	Quantity	Unit Cost	Cost
202-00210	REMOVAL OF CONCRETE PAVEMENT	SY	179	\$ 39.2	\$ 7,016.8
202-00240	REMOVAL OF ASPHALT MAT (PLANING)	SY	791	\$ 9.2	\$ 7,277.2
203-00060	EMBANKMENT MATERIAL (COMPLETE IN PLACE)	CY	15	\$ 91.4	\$ 1,371.0
207-00205	TOPSOIL	CY	55	\$ 27.9	\$ 1,534.5
208-00002	EROSION CONTROL LOG TYPE 1 (12 INCH)	LF	200	\$ 3.8	\$ 760.0
208-00045	CONCRETE WASHOUT STRUCTURE	EA	1	\$ 2,188.5	\$ 2,188.5
208-00070	VEHICLE TRACKING PAD	EA	1	\$ 4,245.2	\$ 4,245.2
208-00103	REMOVAL AND DISPOSAL OF SEDIMENT (LABOR)	HOURL	8	\$ 54.5	\$ 436.0
208-00105	REMOVAL AND DISPOSAL OF SEDIMENT (EQUIPMENT)	HOURL	8	\$ 130.5	\$ 1,044.0
208-00106	SWEEPING (SEDIMENT REMOVAL)	HOURL	12	\$ 190.0	\$ 2,280.0
208-00207	EROSION CONTROL MANAGEMENT	DAY	18	\$ 316.7	\$ 5,700.6
210-01130	RESET GUARDRAIL TYPE 3	LF	132	\$ 131.1	\$ 17,305.2
212-00005	SEEDING (NATIVE)	ACRE	0.07	\$ 1,775.0	\$ 124.3
216-00201	SOIL RETENTION BLANKET (STRAW/COCONUT) (BIODEGRADABLE CLASS 1)	SY	328	\$ 3.8	\$ 1,246.4
304-06007	AGGREGATE BASE COURSE (CLASS 6)	CY	47	\$ 87.4	\$ 4,107.8
403-00720	HOT MIX ASPHALT (PATCHING)(ASPHALT)	TON	9	\$ 399.7	\$ 3,597.3
403-34741	HMA (GRADING SX)(75) (PG 64-22)	TON	131	\$ 173.4	\$ 22,715.4
412-00800	CONCRETE PAVEMENT (8 INCH)	SY	179	\$ 168.2	\$ 30,107.8
506-00209	RIPRAP (9 INCH)	CY	1	\$ 567.0	\$ 567.0
507-00400	ASPHALT SLOPE AND DITCH PAVING (ASPHALT)	TON	3	\$ 958.0	\$ 2,874.0
515-00120	WATERPROOFING (MEMBRANE)	SY	791	\$ 26.6	\$ 21,040.6
609-60011	CURB TYPE 6 (SECTION M)	LF	63	\$ 43.0	\$ 2,709.0
615-00050	EMBANKMENT PROTECTOR TYPE 5	EA	1	\$ 3,202.0	\$ 3,202.0
620-00020	SANITARY FACILITY	EA	1	\$ 316.7	\$ 316.7
626-00000	MOBILIZATION	LS	1	\$45,802.5	\$ 45,802.5
627-00008	MODIFIED EPOXY PAVEMENT MARKING	GAL	24	\$ 950.0	\$ 22,800.0
630-00016	TRAFFIC CONTROL (SPECIAL)	LS	1	\$95,450.0	\$ 95,450.0
Bid Item Total					\$ 307,820
700-70010	F/A Minor Contract Revisions	FA	1	\$ 21,000	\$ 21,000
700-70380	F/A Erosion Control	FA	1	\$ 10,000	\$ 10,000
Bid Item & Force Account Total					\$ 338,820